

QUOTATION

Name of work:- Providing of Auto changeover switch for DG power supply at SL-308 & 309.

S.N	Description of item	Qty	Unit	Rate	Amount
(In words & Figures)					
1	S/F, of 32mm of steel flexible pipe on surface/ open duct as required.	2.00	Mtr		
2	supply, installation, testing and commissioning of wall mounting Auto changeover panel 125A, 4P. with Aluminium bus bar of 125Amp capacity in all bus bars, along with digital ampere meter. digital voltmeter 0-600V-2 nos, selector switch, indicating lamp R, Y B-2 sets, 3 Phase 4 wire ,Digital KWH meter having 1 no. 125Amp contactor for main supply and 1 no. 125Amp contactor for DG supply 1 no. complete as per specification "E"	1.00	Nos		
3	Supplying and drawing of following sizes of FR-LSH PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
a	4x16sqmm	5.00	Mtr.		
4	Dismantling and refixing brass compression type gland up to 400 sq. mm. cable	2.00	Nos		
5	Disconnecting and Dismantalling/refixing damaged Changeover Switch/ MCCB /DB/KWH meter/pole fuse box of any size from site and depositing in store l/c cartage etc. as reqd.	2.00	Nos		

Total Rs.



