

**INDIAN INSTITUTE OF TECHNOLOGY KANPUR****Tender Notice No. 115 /IWD/ED/594****SCHEDULE OF QUANTITY**

Name of work: Modification and maintenance work of electrical installation of House No. 341, 4071, 4093, 4094, 4096, 609, 648.

Name of the Contractor					
S. No	Description of Items	Qty	Unit	Rate in Figures in Rupees	Amount
1	Rewiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable and 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable as earth wire in existing surface/ recessed steel conduit including dismantling as required.				
a)	Group 'B'	15.00	Points		
2	Supplying & drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel / PVC conduit as reqd.				
a)	1 x 1.5 Sq.mm..	50.00	Mtr.		
b)	2 x 1.5 Sq.mm..	50.00	Mtr.		
c)	3 x 1.5 Sq.mm..	100.00	Mtr.		
d)	2 x 4 Sq.mm..	50.00	Mtr.		
e)	3 x 4 Sq.mm..	50.00	Mtr.		
f)	3 x 6 Sq.mm..	30.00	Mtr.		
3	Supplying and drawing telephone cable of 2 pair 0.5 mm dia FRLS PVC insulated annealed copper conductor, unarmored telephone cable in the existing surface/ recessed steel/ PVC conduit as required.	100.00	Mtr.		
4	S & F following piano type switch /socket on existing switch box/cover I/c connection etc as reqd.				
a)	5/6 Amp switch	100.00	Nos.		
b)	2 way 5/6 amp switch	5.00	Nos.		
c)	15/16 Amp. switch	30.00	Nos.		
d)	3 Pin 5/6 Amp. socket outlet	40.00	Nos.		

S. No	Description of Items	Qty	Unit	Rate in Figures in Rupees	Amount
e)	6 Pin 15/16 Amp. socket outlet.	30.00	Nos.		
f)	Telephone socket / jack outlet	5.00	Nos.		
g	Call bell push	5.00	Nos.		
5	Supplying and fixing 3 pin, 5 amp. Ceiling rose on the existing junction box/ wooden block including connection etc. as reqd.	30.00	Nos.		
6	Supplying and fixing brass batten/ angle holder including connection etc. as required.	25.00	Nos.		
7	Supplying and fixing call bell/ buzzer suitable for D.C./A.C. single phase, 230 volts, complete as required.	3.00	Nos.		
8	Supplying and fixing following way, horizontal type three pole and neutral, sheet steel, MCB distribution board, 415 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator)				
a)	16-way , Double door	1.00	Nos.		
9	Supplying and fixing 5 amps to 32 amps rating, 240 volts, 'C' series, MCB suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as reqd.				
a)	Single Pole	10.00	Nos.		
10	S & F following rating double pole (single phase & neutral) 240 volts RCCB (ELCB), having sensivity current up to 300 mA in the existing MCB DB complete with connection,testing & commissioning etc as reqd.				
a)	63 Amp	5.00	Nos.		
11	Earthing with G.I earth pipe 4.5 mtr long. 40 mm dia including accessories, and providing masonary enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal and salt as required.	4.00	Set		
12	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing as required.	100.00	Mtr		
13	S & F following piano type switch /socket on existing switch box/cover I/c connection etc as reqd.				
a)	Fan regulator switch type rotary Dimmer	20.00	Nos.		

S. No	Description of Items	Qty	Unit	Rate in Figures in Rupees	Amount
14	Drawing of optical cable enhanced cat 5/cat 6/telephone/networking /power cable in existing steel conduit pipe/GI /HDPE pipe including numbering of networking wire from room to rack as reqd.	150.00	Mtr.		
15	Providing and fixing casing and capping in place of defective and damaged wood batten including dismantling of batten and wire & relaying of wires as required complete.				
a)	20 x 12 mm	100.00	Mtr.		
b)	25 x 16 mm	50.00	Mtr.		
c)	32x 16 mm	50.00	Mtr.		
d)	38 x 16 mm	50.00	Mtr.		
16	S & F wooden board of following sizes on surface or in recessed with suitable size of phenolic laminated sheet cover in the front etc as reqd.				
a)	100 mm x 100 mm	20.00	Nos.		
b)	175 mm x 100 mm	20.00	Nos.		
c)	200 mm x 150 mm	10.00	Nos.		
d)	200 mm x 250 mm	10.00	Nos.		
17	Dismantling damaged DB/TPN Switches/ loose wire boxes along with all accessories and depositing the same in the store as reqd.	5.00	Nos.		
18	Supplying, fixing, connecting, commissioning and testing of the following luminaries light fixtures complete with all accessories and without lamp as required complete.				
a)	Drum light cat No.03 PV / 02 decon make or equivalent.	10.00	Nos.		
b)	Wall bracket Decon make cat. no. 0553 or equivalent.	10.00	Nos.		
c)	Bulk head fitting suitable for 60W GLS lamp, Philips make or equivalent.	10.00	Nos.		
19	Dismantling and refixing of switch / socket /regulator I/c cleaning, connecting, commissioning etc as reqd.	100.00	Nos.		

S. No	Description of Items	Qty	Unit	Rate in Figures in Rupees	Amount
20	Supply, Installation, testing & commissioning of AC ceiling fan of following sweep 220 volts without regulator I/c wiring the down rods of standard length up to 30 cm with 1.5 sq.mm. PVC insulated copper conductor single core cable etc as reqd.				
a)	1200 mm	20.00	Nos		
b)	1400 mm	6.00	Nos.		
21	S & F 3 mm thick phenolic laminated sheet on existing board with brass screw & cup washer etc as reqd.	5000.00	Sq.inch		
22	Fixing of RJ-45 modular box with cover plate or I/o box for internet on surface/ recessed cutting the wall making good the same as required. (box and cover plate will be supplied by dept.)	10.00	Nos.		
23	Dismantling and refixing of wooden board of any sizess on surface or in recessed etc as reqd.	40.00	Nos.		
	Total Rs.				