## INDIAN INSTITUTE OF TECHNOLOGY KANPUR Tender Notice No. 74/Lift/2020

## SCHEDULE OF QUANTITY

Name of Work: Supplying, installation, testing & commissioning of 8 passenger elevator at Yoga centre, IIT Kanpur with 05 year AMC after 01 year free maintenance warranty period.

Name of the Contractor						
S. No	1	Description of Items	Qty	Unit	Rate in Figures in Rupees	Amour
1	Part-A: Supplying, installation, testing & commissioning of 8 passenger					
	elevator as per details given technical specification, etc. complete as required.					
	Designation of lift:	Passenger Elevator				
	Type and capacity	08 passenger 544 Kgs				
	Speed	1.0 m/s				
	Drive	VF Regenerative (Closed Loop)				
	Location of machine room	Machine roomless- Gearless				
	Total Travel	08 Mtrs.				
	Serving	0 to 2 nd floor, Floor Designation will be 0,1,2				
	No of stops	3 (G+2 upper floors)				
	Lift well size	2100 mm W x 1850 mm D				
	Power supply	415 Volts (3 phase, 50 Cycles AC)				
	Auxiliary	single phase 220 V 50 Cycle AC)				
	Lift Car size inside	1100 mm W x 1300 mm D x 2200 mm H				
	Pt Depth	1350 mm				
	Head Room	4200 mm				
	Car Enclosure					
	Car Ceiling	CT 002-SS Hairline Finish- 304 Grade				
	Car Panels	Stainless steel (1.5 mm) Hairline Finish -304 Grade				
	Car Flooring	Stainless steel (1.5 mm) Hairline Finish				
	Car illumination	sleek (small ciculator LED lights)				
	No. Entrance	One location front				
	Car Entrance	Centre opening power doors SS Hairline Finish-304 Grade				
	Door Safety	Full Height Infra red safety curtains				
	Landing Entrance	Centre opening power doors SS Hairline Finish-304 Grade				
	Clear Opening	800 MM (W) x 2000 (H) Lintel-2200 mm				
	Control	Full Collective Simplex				
	Indicators					
	Car	KDS 300 FH COP 1 nos- round surface				
		mounted braile Buttons with 7 segments Indication Red				
	Landing	Round surface Mounted Braile Buttons with DOT Matrix Indication Red				
	Operation: Without attendent automatic operation with door protection device.					
	* Digital Hall position Indicator					
	* Overload warning indicator and service cabinet.					
	* Battery operation alarm bell and emergency light					
	* Firemans switch at main body					
	* Signals have S.S phase plate.					
	* A. R D (Automatic Risk Device)					
	* Door operation: Automatic (DC door operation)					
	* Car panels: Stainless steel (1.5 mm) panels in hairline finish		1.00	No.		
_	(Note: The annual maintenar	al maintenance contract of above lift for 5 years nee of the lift shall be w.e.f after expiry of defect om the date of completion of work.	1.00	No.		
	Total Rs.	E				