


## QUOTATION

Name of Work:- Repairing & Maintenance of Solar water heating system installed at RA Tower.

S.No	Description of work	Qty.	Unit	Rate	Amount
(In words & Figures)					
1	Providing & fixing 50 mm thick more than 48 Kg/cu Mtr glass wool insulation wrapped with wire mesh etc as required complete on following size hot water pipe line.	15.00	Sq Mtr.		
2	Providing & fixing 26 swg thick aluminium cladding bend with screw make Hindalco or its equivalent approved make etc as required complete.	15.00	Mtr.		
3	Supplying, fixing, testing & commissioning of CPVC coupler 15 mm make Prince or its equivalent make with solvent cement etc as reqd.	26.00	Nos.		
4	Supply fixing connecting & commissioning of MS clamp. as required complete	60.00	Nos.		
5	Supplying & fixing of CPVC brass elbow 15 mm etc as reqd.	25.00	Nos.		
6	Supply fixing connecting & commissioning of 2/3 kW heating element in geyser including dismantling and refixing as required complete	31.00	Nos.		
7	Supply fixing connecting & commissioning of thermostat suitable for geyser. as required complete	31.00	Nos.		

Total Rs.

  
RAGHAVENDRA SINGH  
संस्थापक अभियंता (वि.) E.E. (Elect)  
संविदांक/२०१६/२०१७/३०००  
I.W.D., I.E.T., A.P.

