

QUOTATION

Name of work: Electrical Maintenance work at south side residence as per enclosed complaints.


| S.No. | Description | Qty. | Unit | Rate (In words & figures) | Amount |
|-------|--|-------|--------|------------------------------|--------|
| 1 | Rewiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable and 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable as earth wire in existing surface/ recessed steel conduit including dismantling as required. | | | | |
| a | Group 'A' | 3.00 | Points | | |
| 2 | Supplying & drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel / PVC conduit as reqd. | | | | |
| a | 3 x 1.5 Sq.mm.. | 27.00 | Mtr. | | |
| b | 3 x 4 Sq.mm.. | 48.00 | Mtr. | | |
| 3 | S & F following piano type switch /socket on existing switch box/cover I/c connection etc as reqd. | | | | |
| a | 5/6 Amp switch | 14.00 | Nos. | | |
| b | 2 way 5/6 amp switch | 2.00 | Nos. | | |
| c | 15/16 Amp. switch | 7.00 | Nos. | | |
| d | 3 Pin 5/6 Amp. socket outlet | 7.00 | Nos. | | |
| e | 6 Pin 15/16 Amp. socket outlet. | 6.00 | Nos. | | |
| 4 | Supplying and fixing 3 pin, 5 amp. Ceiling rose on the existing junction box/ wooden block including connection etc. as reqd. | 2.00 | Nos. | | |
| 5 | Supplying and fixing brass batten/ angle holder including connection etc. as required. | 6.00 | Nos. | | |

| O. | Description | Qty. | Unit | Rate (In words & figures) | Amount |
|----|---|---------|-------|------------------------------|--------|
| 6 | Supplying and fixing 5 amps to 32 amps rating, 240 volts, 'C' series, MCB suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as reqd. | | | | |
| a | Single Pole | 2.00 | Nos. | | |
| 7 | S & F following rating double pole (single phase & neutral) 240 volts RCCB (ELCB), having sensivity current up to 300 mA in the existing MCB DB complete with connection,testing & commissioning etc as reqd. | | | | |
| a | 40 Amp | 2.00 | Nos. | | |
| 8 | Laying UTP cable enhanced cat 5/cat 6 cable in existing steel conduit pipe/GI pipe/ raceway / RCC pipe as reqd. the cost shall also include numbering of networking wire from room to rack as reqd. (wire will be supplied by dept) | 5.00 | Mtr. | | |
| 9 | S & F wood board of following sizes (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in the front etc as reqd. | | | | |
| a | 100 mm x 100 mm | 8.00 | Nos. | | |
| b | 175 mm x 100 mm | 5.00 | Nos. | | |
| 10 | Dismantling and refixing of wood board of any size on surface or in recessed etc as reqd. | 2.00 | Nos. | | |
| 11 | Dismantling damaged DB/TPN Switches/ loose wire boxes along with all accessories and depositing the same in the store as reqd. | 2.00 | Nos. | | |
| 12 | S & F 3 mm thick phenolic laminated sheet on existing board with brass screw & cup washer etc as reqd. | 1000.00 | Sq.cm | | |
| 13 | Dismantling and refixing of switch / socket /regulator I/c cleaning, connecting, commissioning etc as reqd. | 17.00 | Nos. | | |

| No. | Description | Qty. | Unit | Rate | Amount |
|-----|--|-------|------|----------------------|--------|
| | | | | (In words & figures) | |
| 14 | Supply, Installation, testing & commissioning of AC ceiling fan of following sweep 220 volts without regulator I/c wiring the down rods of standard length up to 30 cm with 1.5 sq.mm. PVC insulated copper conductor single core cable etc as reqd. | | | | |
| a | 1200 mm | 7.00 | Nos. | | |
| 15 | Supply & fixing of 12 W surface mounted light ec.as reqd. make Havells OR equivalent approved make. | 5.00 | Nos. | | |
| 16 | Locating fault in wiring rectifying removing & restoring supply the same & making good the damages etc as reqd. | 5.00 | Nos. | | |
| 17 | Supplying, fixing, connecting, commissioning and testing of the following luminaries light fixtures complete with all accessories and without lamp as required complete. | | | | |
| a | Drum light cat No.03 PV / 02 decon make or equivalent. | 2.00 | Nos. | | |
| b | Wall bracket Decon make cat. no. 0553 or equivalent. | 2.00 | Nos. | | |
| c | Bulk head fitting suitable for 60W GLS lamp, Philips make or equivalent. | 2.00 | Nos | | |
| d | Wall light stylo fitting 14W Havells make or equivalent. | 2.00 | Nos | | |
| 18 | Supply, Installation of exhaust fan, 900 rpm 220 volt AC, 50 Hz of following sweep in the existing opening I/c connection, testing, commissioning etc as read. | | | | |
| a | 300 mm | 4.00 | Nos. | | |
| b | 380 mm | 1.00 | Nos. | | |
| 19 | S & F following piano type switch /socket on existing switch box/cover I/c connection etc as reqd. | | | | |
| a | Fan regulator socket type rotary step | 16.00 | Nos. | | |
| 20 | Supply and installation of 400mm sweep AC 230/250 volts, 50 Hz wall mounting revolving fan with brackets etc complete.(make Havells) | 1.00 | Nos. | | |

| No. | Description | Qty. | Unit | Rate | Amount |
|-----|---|-------|------|----------------------|--------|
| | | | | (In words & figures) | |
| 21 | S & F 40 amp to 63 amp rating 240 volts 'C' curve 10 kA MCB of following pole in the existing MCB DB complete with connection, testing & commissioning etc as reqd. (legrand) | | | | |
| a | Double pole | 2.00 | Nos. | | |
| 22 | S & F metal enclosure suitable for DP/TPN MCB / DP ELCB on surface or recessed etc as reqd. | 1.00 | Nos. | | |
| 23 | Supplying, fixing, connecting, commissioning and testing of the following luminaries light fixtures complete with all accessories and with lamp as required complete. | | | | |
| a | LED tube light fitting (2 X 18 / 20 Watt. LED) surface mounting luminaires wipro make or its equivalent approved make etc as reqd. | 1.00 | Nos. | | |
| 24 | Providing and fixing following sizes of PVC casing and capping on surface as reqd. | | | | |
| a | 20 x 12 mm | 24.00 | Mtr. | | |
| b | 25 x 16 mm | 13.00 | Mtr. | | |
| 25 | Supply and laying of HDPE pipe ISI mark of 25 mm (8Kg / cm ²) size inner dia, 2mm thick I/c cartage loading & unloading etc. as reqd. | | | | |
| a | Direct in ground I/c excavation, sand cushioning, protective covering and refilling the trench etc. as reqd. | 5.00 | Mtr. | | |
| b | On surface with MS clamp | 2.00 | Mtr. | | |

Total Rs


राघवेंद्र सिंह
RAGHVENDRA SINGH
 अधिकाणी अधिवक्ता (वि०) E.E. (Elect.)
 सं. नि. वि. मा. प्र. संस्थान, काभार
 I.W.D., I.L.T., Kambar