


QUOTATION

Name work : Repairing of street light near Type-2,4, KV school , Old Sport Complex, Southern Lab, main gate etc. as per enclosed complaints.

S.N.	Description	Qty	Unit	Rate	Amount
				(In Words & Figures)	
1	Supplying and making straight through joint with heat shrinkable kit including ferrules and other jointing materials for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.				
a	2x16sqmm	2.00	Each		
2	Providing brick work (in width 225 mm or more) with F.P.S. bricks of class designation 7.5 in cement mortar 1:4 (1 cement : 4 coarse sand) at all levels.	1.00	Cum		
3	Providing 15mm thick cement plaster of mix 1:4 (1 cement : 4 fine sand) at all levels.	2.00	Sqm		
4	Dismantling and refixing brass compression type gland up to 35 sq. mm. cable	15.00	Nos.		
5	Digging cable trench/lifting brick/s and cable for locating fault and refilling the trench, ramming & making good the same as reqd.	63.00	Mtr.		
6	Locating fault in the cable lines with meggar etc and rectifying removing & restoring the same and making good the damages etc as required.				
a	upto 35 sqmm	10.00	Nos.		
7	Dismantling cross arm / street light brakcet/street light fitting from pole complete as required.	1.00	Nos.		
8	Dismantling,repairing cleaning and commissioning of all type of street light fitting on pole/ walls etc. as reqd.	1.00	Nos.		

S.N.	Description	Qty	Unit	Rate	Amount
				(In Words & Figures)	
9	S & F of following rating & poles 240 volts 'C' curve 10 kA MCB in the existing MCB DB complete with connection, testing & commissioning etc as reqd.				
a	Single Pole (40A to 63A)	1.00	Nos.		
10	S/F testing commissioning of street light Luminures.ENDURA CITYLITE PLAT INUM PLUS 35W LED Energy saving and environmental friendly long life LED street light made up of pressure die cast aluminium housing with high power LED as lighting source and lens embedded PC cover having IP65 protection and Impact resistance of IK07 with 10KV Built-in Surge Protection Device.,make:havells or its equivalent, on the existing street light pole complete as required.	1.00	Nos.		
11	Supplying, fixing, connecting, commissioning and testing of double side connection following luminaries light fixtures complete with all accessories and with lamp as required complete.				
a)	LED tube with fitting 18 / 20 Watt.	6.00	Nos.		
12	Supplying and drawing of following sizes of FR PVC insulated copper conductor, 3 core round cable of following size in the existing surface/ recessed steel/ PVC conduit as required.				
a	1.5 Sq.mm	8.00	Mtrs.		
13	Fabrication, supplying & fixing of box of required size made out of 2mm thick CRCA sheet duly powder coated & openable from top-bottom or front required & fixing the same complete as required.	20.00	Kg		
Say Rs.					


 अधिकांश अविष्ठा (वि०) E.E. (Elect.)
 संचालक, मासिक संस्थान, कानपुर
 I.W.D., I.I.T., Kanpur.
