

## QUOTATION

**Name of work:- Digging & making new foundation at the place of old foundation for fixing & connecting Telephone DP near 452 in Type-4 Area.**

S.No.	Description	Qty.	Unit	Rate (In words & Figures)	Amount
1	Providing brick work (in width 225 mm or more) with F.P.S. bricks of class designation 7.5 in cement mortar 1:4 (1 cement : 4 coarse sand) at all levels.	1.00	Cum		
2	Providing 15mm thick cement plaster of mix 1:4 (1 cement : 4 fine sand) at all levels.	10.50	sqm		
3	Fixing & connecting of telephone DP/network rack ( HUB ) on wall floor with suitable brick foundation on bolts and nut etc. as reqd.	1.00	Nos.		
4	Digging cable trench, lifting brick & cable for locating fault and relaying the cable i/c refilling the trench, extra sand if required shall be i/c in the item of following size. as required.				
a)	not exceeding 35 sq.mm..	22.34	Mtr		
5	Dismantling and removing of old foundation for telephone DP.	1.00	Each		
6	Dismantling Telephone DP/ loose wire boxes along with all accessories and depositing the same in the store as reqd.	1.00	Nos.		
7	Supplying & making indoor end termination with brass compression type gland up to 35 sq.mm cable.				
a)	35 sq. mm	2.00	Nos.		

S.No.	Description	Qty.	Unit	Rate (In words & Figures)	Amount
8	Dismantling & refixing brass compression type gland up to 35 sq.mm. cable.	2.00	Nos.		
<b>Total Rs</b>					

  
 अधिकाारी अतिराला (मिने) / ए.ए. (मिने.)  
 सारनिर्दिष्ट. मरु मीठ संस्थान कासपुर  
 I.W.D., I.L.F. Kasapur  
