

QUOTATION

Name of work:-Replacement of old and faulty power cable,feeding power to main DB of A & B block of old old SBRA in the campus.


S.No.	Description	Qty.	Unit	Rate	Amount
(In words & Figures)					
1	Supplying and making indoor end termination with brass compression gland, aluminum lugs for following size of PVC insulated & PVC sheathed/XLPE aluminum cable of 1.1kV grade as reqd.				
a)	3-1/2x 50 sq.mm. (35mm)	2.00	Nos.		
2	Providing, laying and fixing following dia G.I. pipe (medium class) in ground complete with G.I. fittings including trenching (75 cm deep) and re-filling etc as required				
a)	50mm dia	10.00	Mtr.		
3	S & Laying of one no. XLPE cable aluminum conductor steel armoured power cable of 1.1kV grade of size 3-1/2 x 50 sq.mm. in following manners.				
a)	In Ground including excavation, sand cushioning brick protecting covering and refilling the trench etc. as reqd.	45.00	Mtr		
b)	In pipe	10.00	Mtr		
c)	In open duct	5.00	Mtr		
d)	On surface with MS clamp	5.00	Mtr		

S.No.	Description	Qty.	Unit	Rate	Amount
-------	-------------	------	------	------	--------

(In words & Figures)

4	Dismantling & refixing brass compression type cable gland up to 400 sq.mm. cable.	10.00	Nos.		
---	---	-------	------	--	--

Total Rs


 अधिकारी अभियन्ता (वि)/E.E. (Elect)
 कार्यालय, माउ पीठ संजयन, कानपुर
 I.W.D., I.E. Kannur

