

QUOTATION

Subject Providing and fixing 5 A & 15 A power points, net points, light fittings etc. at WL Corrosion Lab 2, WL Near Gate 04, Samtal Reception, SE PSEUDO and different labs and offices in academic area on complaint basis.

SL No.	DESCRIPTION	QTY	UNIT	RATE (In words & Figures)	AMOUNT
1	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed steel conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required.				
a	Group C	8.00	Point		
2	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
a	3 x 1.5 sq. mm	15.00	Metre		
b	3 x 2.5 sq. mm	11.00	Metre		
c	3 x 4 sq. mm	19.00	Metre		
3	Supplying and drawing following pair 0.5 mm dia FRLS PVC insulated annealed copper conductor, unarmored telephone cable in the existing surface/ recessed steel/ PVC conduit as required.				
a	2 Pair	22.00	Metre		

SL No.	DESCRIPTION	QTY	UNIT	RATE (In words & Figures)	AMOUNT
4	Supplying and fixing of following sizes of steel conduit along with accessories in surface/recess including painting in case of surface conduit, or cutting the wall and making good the same in case of recessed conduit as required.				
a	20 mm	10.00	Metre		
5	Supplying and fixing following piano type switch/ socket on the existing switch box/ cover including connections etc. as required.				
a	5/6 amps switch	1.00	No.		
6	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
a	5/6 A switch	16.00	No.		
b	15/16 A switch	6.00	No.		
c	3 pin 5/6 A socket outlet	12.00	No.		
d	6 pin 15/16 A socket outlet	4.00	No.		
7	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.				
a	1or 2 Module	5.00	No.		
b	3 Module	5.00	No.		
c	4 Module	2.00	No.		
d	6 Module	2.00	No.		

SL No.	DESCRIPTION	QTY	UNIT	RATE (In words & Figures)	AMOUNT
8	Installation of exhaust fan in the existing opening, including making good the damage, connection, testing, commissioning etc. as required.				
a	Upto 450 mm sweep	1.00	No.		
9	Supplying and fixing following rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
a	Double pole 5 A to 32 A	1.00	No.		
10	Supplying and fixing single pole blanking plate in the existing MCB DB complete etc. as required.	2.00	No.		
11	S & F following size of steel flexible pipe alongwith the accessories on surface etc as required				
a	20 mm	15.00	Meter		
12	Supply and fixing of 32 x 20 mm DLP mini- trunking white-system with independent cover etc. as required complete.	47.00	Meter		
13	Supply and fixing of 105 x 50 mm DLP trunking white-system but without cover and partion etc. as required complete.	1.00	Meter		
14	Supply and fixing of following accessories suitable for 105 mm x 50 mm size plastic trunking white system.				
a	End cap	2.00	Nos.		

SL No.	DESCRIPTION	QTY	UNIT	RATE (In words & Figures)	AMOUNT
15	Supplying, installation of Clip-on frame with finishing plate for 85mm cover for DLP plastic trunking 105mm x 50mm etc. as reqd.				
a	3 module	1.00	Nos.		
b	6 module	1.00	Nos.		
16	Dismantling, disconnecting old damaged unserviceable fl fitting/ exhaust fan/ ceiling fan/ bulkhead fitting with bracket etc. as reqd. and depositing in sectional store.	3.00	Nos.		
17	Supplying and fixing following size/ modules, plastic box for modular switches in recess etc as required.				
a	1 or 2 Module	3.00	Nos.		
b	3 Module	4.00	Nos.		
c	6 Module	2.00	Nos.		
18	S & F metal enclosure suitable for DP/TPN MCB / DP ELCB on surface or recessed etc as reqd.	1.00	Nos.		
19	Supply and installation of 400mm sweep AC 230/250 volts, 50 Hz wall mounting revolving fan with brackets etc complete.	6.00	Nos.		
20	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				

SL No.	DESCRIPTION	QTY	UNIT	RATE (In words & Figures)	AMOUNT
--------	-------------	-----	------	------------------------------	--------

a	RJ 11 Telephone socket	1.00	Nos.		
---	------------------------	------	------	--	--

21	Supply and fixing of following LED light fixture with Electronic driver, LED lamp, reflector, diffuser, MS body/housing holder etc. complete with all fixing accessories and lamp as required complete.				
----	---	--	--	--	--

a	LED Flood Light Outdoor 100 Watt Led Outdoor Flood Light,CROMPTON or its equivalent approved make.	1.00	Nos.		
---	--	------	------	--	--

Total Rs.



अधिकायी जमियन्ता (वि.)/ए.ए. (फा.वि.)
अधीकरी, माड ग्रीड सरधान, कानपुर
I.W.D., I.T., Kanpur.

