


QUOTATION

Name of work:-Installation of Secure energy meters in LT panels at various substations and in feeder pillars where energy meter either not working or not available in the campus for preparing energy audit reports.

S.No.	Description	Qty.	Unit	Rate	Amount
1	Supplying & drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel / PVC conduit as reqd.				
a)	1 x 1.5 Sq.mm..	50.00	Mtr.		
2	Supplying, installation, testing & commissioning of kWh meter LCD Panel type in AMF panel.(Secure make Elite 446) or equivalent.	13.00	Nos.		
3	Supplying, installation, testing & commissioning of current transformer of following rating in the AMF panel.				
a	600/5Amp	3.00	Nos.		
b	400/5Amp	6.00	Nos.		
c	240/5Amp or 250/5Amp	9.00	Nos.		
d	150/5Amp or 125/5 Amp.	6.00	Nos.		
4	Dismantling damaged DB/TPN Switches/KWH Meter loose wire boxes along with all accessories and depositing the same in the store as reqd.	5.00	Nos.		

Total Rs


अधिसारी अभियन्ता (वि०)/E.E. (Elect.)
संवि०वि०, भा० प्र० संस्थान, कानपुर
I.W.D. I.I.T. Kanpur

(Noble)