

QUOTATION


Name of work -:Electrical maintenance works at SS1, FA/C203, 454 KVS, H No. 230 Type-II, E-2, D-2, N-5, F-1, S-6, L-6 Old SBRA, Susta media lab, H No. 2037, 2065, 2075, 275 Type-2, Flat 701, 305, 2081, FA/C604, Kislaya Nursery School Type-2, FA-D102 C604, New SBRA Z-11, Z-12 Z-18, AA12, Block A FA/502, south side residences as per enclosed complaints.

S.No	Description	Qty	Unit	Rate (In words & Figures)	Amount
1	Supplying & drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel / PVC conduit as reqd.				
1.1	3 x 1.5 Sq.mm..	10.87	Mtr.		
1.2	3 x 4 Sq.mm..	5.00	Mtr.		
2	S & F following piano type switch /socket on existing switch box/cover I/c connection etc as reqd.				
2.1	5/6 Amp switch	16.00	Nos.		
2.2	2 way 5/6 amp switch	1.00	Nos.		
2.3	15/16 Amp. switch	3.00	Nos.		
2.4	3 Pin 5/6 Amp. socket outlet	6.00	Nos.		
2.5	6 Pin 15/16 Amp. socket outlet.	3.00	Nos.		
2.6	Call bell push	1.00	Nos.		
3	Supply, fixing, following modular type switch / socket on existing modular plate & switch box including connectins but excluding modular plate etc. as reqd.				
3.1	5/6 Amp switch	37.00	Nos.		
3.2	15/16 Amp. switch	7.00	Nos.		

S.No	Description	Qty	Unit	Rate (In words & Figures)	Amount
3.3	3 Pin 5/6 Amp. socket outlet	15.00	Nos.		
3.4	6 Pin 15/16 Amp. socket outlet.	2.00	Nos.		
3.5	Bell Push	1.00	Nos.		
3.6	Fan regulator socket type rotary step	4.00	Nos.		
3.7	Blanking plate	5.00	Nos.		
4	S & F following size/modules, GI box along with modular base and cover plate for modular switches in recess etc.as required.				
4.1	3 module	1.00	Nos.		
4.2	4 module	1.00	Nos.		
4.3	6 module	1.00	Nos.		
5	S/F following modular base & cover plate on existing modular metal boxes etc. as reqd.				
5.1	1 or 2 module	3.00	Nos.		
5.2	3 module	1.00	Nos.		
5.3	4 module	5.00	Nos.		
5.4	6 module	7.00	Nos.		
5.5	8 module	1.00	Nos.		
6	Supplying and fixing 3 pin, 5 amp. Ceiling rose on the existing junction box/ wooden block including connection etc. as reqd.	2.00	Nos.		
7	Supplying and fixing brass batten/ angle holder including connection etc. as required.	9.00	Nos.		

S.No	Description	Qty	Unit	Rate (In words & Figures)	Amount
8	Supplying and fixing call bell/ buzzer suitable for D.C./A.C. single phase, 230 volts, complete as required.	1.00	Nos.		
9	Supplying and fixing 5 amps to 32 amps rating, 240 volts, 'C' series, MCB suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as reqd.				
9.1	Single Pole	4.00	Nos.		
10	Drawing of optical cable enhanced cat 5/cat 6/telephone/ networking /power cable in existing steel conduit pipe/GI /HDPE pipe including numbering of networking wire from room to rack as reqd.	274.05	Mtr.		
11	Providing and fixing following sizes of PVC casing and capping on surface as reqd.				
11.1	20 x 12 mm	11.00	Mtr.		
12	Supply / fixing and connecting & commissioning following CFL / lamps in existing fitting as reqd.(Make- Phillips or its equivalent)				
12.1	LED tube light 18 / 20 Watt.	4.00	Nos.		
13	Dismantling and refixing of switch / socket /regulator I/c cleaning, connecting, commissioning etc as reqd.	35.00	Nos.		
14	Supply and installation of 400mm sweep AC 230/250 volts, 50 Hz wall mounting revolving fan with brackets etc complete.	3.00	Nos.		
15	Supply, Installation, testing & commissioning of AC ceiling fan of following sweep 220 volts without regulator I/c wiring the down rods of standard length up to 30 cm with 1.5 sq.mm. PVC insulated copper conductor single core cable etc as reqd.				

S.No	Description	Qty	Unit	Rate	Amount
				(In words & Figures)	
15.1	1200 mm	2.00	Nos		
16	S & F 3 mm thick phenolic laminated sheet on existing board with brass screw & cup washer etc as reqd.	1440.00	Sq.inch		
17	Locating fault in wiring rectifying removing & restoring supply the same & making good the damages etc as reqd.	11.00	Nos.		
18	Dismantling and refixing of wooden board of any sizess on surface or in recessed etc as reqd.	5.00	Nos.		
Total Rs.					


 अधिकायी अधिवक्ता (वि.) E.E. (Elect.)
 संचालक, वाटवरी संस्थान, काजपुर
 (W.D., L.L.L. Karpur)
