

QUOTATION

Name of work -:Electrical maintenance works at Y4, W12, Z-12, Z18 New SBRA, FA/B204, H No.409, B304, B203, 415, FA/C-501, FA/C-502 Type-4, Flat no. 304, H No. 206, 239, 2004 Type-2, H2, X10, G-6, C-6 Old SBRA, New Main Gate2 Police check post, A1, A2, A3, V F A, R3 Media lab, south side residences as per enclosed complaints.

S.No	Description	Qty	Unit	Rate	Amount
				(In words & Figures)	
1	Supplying & drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel / PVC conduit as reqd.				
1.1	3 x 1.5 Sq.mm..	7.32	Mtr.		
1.2	3 x 4 Sq.mm..	48.00	Mtr.		
2	Supplying and drawing telephone cable of 2 pair 0.5 mm dia FRLS PVC insulated annealed copper conductor, unarmored telephone cable in the existing surface/ recessed steel/ PVC conduit as required.	69.00	Mtr.		
3	S & F following piano type switch /socket on existing switch box/cover I/c connection etc as reqd.				
3.1	5/6 Amp switch	8.00	Nos.		
3.2	15/16 Amp. switch	2.00	Nos.		
3.3	3 Pin 5/6 Amp. socket outlet	3.00	Nos.		
3.4	6 Pin 15/16 Amp. socket outlet.	3.00	Nos.		
3.5	Telephone socket / jack outlet	2.00	Nos.		
4	Supply, fixing, following modular type switch / socket on existing modular plate & switch box including connectins but excluding modular plate etc. as reqd.				
4.1	5/6 Amp switch	10.00	Nos.		

S.No	Description	Qty	Unit	Rate	Amount
(In words & Figures)					
4.2	15/16 Amp. switch	6.00	Nos.		
4.3	3 Pin 5/6 Amp. socket outlet	4.00	Nos.		
4.4	6 Pin 15/16 Amp. socket outlet.	5.00	Nos.		
4.5	Blanking plate	10.00	Nos.		
4.6	Telephone socket outlet	2.00	Nos.		
4.7	Bell Push	1.00	Nos.		
5	S & F following size/modules, GI box along with modular base and cover plate for modular switches in recess etc.as required.				
5.1	1/2 module	2.00	Nos.		
6	S/F following modular base & cover plate on existing modular metal boxes etc. as reqd.				
6.1	1 or 2 module	4.00	Nos.		
6.2	3 module	2.00	Nos.		
6.3	4 module	2.00	Nos.		
6.4	6 module	2.00	Nos.		
6.5	8 module	1.00	Nos.		
7	Supplying and fixing brass batten/ angle holder including connection etc. as required.	3.00	Nos.		
8	Supplying and fixing call bell/ buzzer suitable for D.C./A.C. single phase, 230 volts, complete as required.	1.00	Nos.		

S.No	Description	Qty	Unit	Rate	Amount
(In words & Figures)					
9	S & F following rating double pole (single phase & neutral) 240 volts RCCB (ELCB), having sensivity current up to 300 mA in the existing MCB DB complete with connection,testing & commissioning etc as reqd.				
9.1	63 Amp	1.00	Nos.		
10	Supplying & drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel / PVC conduit as reqd.				
10.1	2 x 10 Sq.mm..	6.50	Mtr.		
11	S & F wooden board of following sizes on surface or in recessed with suitable size of phenolic laminated sheet cover in the front etc as reqd.				
11.1	100 mm x 100 mm	2.00	Nos.		
11.2	175 mm x 100 mm	3.00	Nos.		
11.3	200 mm x 250 mm	1.00	Nos.		
12	S & F 40 amp to 63 amp rating 240 volts 'C' curve 10 kA MCB of following pole in the existing MCB DB complete with connection, testing & commissioning etc as reqd. (legrand or its equivalent as approved make)				
12.1	Single Pole	2.00	Nos.		
13	Drawing of optical cable enhanced cat 5/cat 6/telephone/ networking /power cable in existing steel conduit pipe/GI /HDPE pipe including numbering of networking wire from room to rack as reqd.	3.90	Mtr.		
14	Providing and fixing following sizes of PVC casing and capping on surface as reqd.				
14.1	20 x 12 mm	36.00	Mtr.		

S.No	Description	Qty	Unit	Rate	Amount
				(In words & Figures)	
14.2	25 x 16 mm	5.00	Mtr.		
15	Supply / fixing , testing & commissioning of 12W LED. Slim surface mounted round LED panel al. die cast body with premium diffuser to ensure glare free as required complete LED make Havells or its equivalent make etc as reqd	3.00	Nos.		
16	Supplying, fixing, connecting, commissioning and testing of the following luminaries light fixtures complete with all accessories and without lamp as required complete.				
16.1	Bulk head fitting suitable for 60W GLS lamp, Philips make or equivalent.	1.00	Nos		
17	Supply / fixing and connecting & commissioning following CFL / lamps in existing fitting as reqd.(Make- Phillips its equivalent as approved make))				
17.1	LED bulb 5W to 10 W	8.00	Nos.		
18	Dismantling and refixing of switch / socket /regulator I/c cleaning, connecting, commissioning etc as reqd.	19.00	Nos.		
19	Dismantling damaged DB/TPN Switches/ loose wire boxes along with all accessories and depositing the same in the store as reqd.	1.00	Nos.		
20	Supply and installation of 400mm sweep AC 230/250 volts, 50 Hz wall mounting revolving fan with brackets etc complete.	1.00	Nos.		
21	S & F 3 mm thick phenolic laminated sheet on existing board with brass screw & cup washer etc as reqd.	370.00	Sq.inch		
22	Locating fault in wiring rectifying removing & restoring supply the same & making good the damages etc as reqd.	3.00	Nos.		
23	Dismantling and refixing of wooden board of any sizess on surface or in recessed etc as reqd.	7.00	Nos.		

S.No	Description	Qty	Unit	Rate	Amount
------	-------------	-----	------	------	--------


(In words & Figures)

24 Supply, Installation, testing & commissioning of AC ceiling fan of following sweep 220 volts without regulator I/c wiring the down rods of standard length up to 30 cm with 1.5 sq.mm. PVC insulated copper conductor single core cable etc as reqd.

24.1 1200 mm 1.00 Nos

25 Supplying, fixing, connecting, testing & commissioning 10-60A, single phase meter(Cat no. SPPB152A111000OC01, HPL make) 230V, 50 hz, digital LCD type electronic kWh electronic meter i/c sealing the same (sealing material will be supplied by the dept.) Gurantee car having serial no. of the meter to be submitted in the dept. etc. as reqd. 1.00 Nos.

Total Rs


 अधिकारी (विद्युत) ए. डी. शर्मा,
 पंचसिद्धि वास्तु संस्था, काठमाडौं
 (W.D. I.T. Khum)

20