


QUOTATION

Name of work :- Replacement of defective 05 pair jelly filled armoured telephone cable at DP near H.No. 404 to H. No. 408 as per enclosed request from IITK.

S.No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
				(In words & Figures)	
1	Supplying and Laying, connecting and commissioning 5 pairs jelly filled armoured telephone cable PVC insulated and PVC sheathed annealed tinned copper conductor.				
1.1	In Ground including excavation, sand cushioning brick protecting covering and refilling the trench etc. as reqd.	75.00	Mtr		
1.2	In pipe	5.00	Mtr		
1.3	On surface with MS clamp	1.00	Mtr		
2	Providing, laying and fixing following dia G.I. pipe (medium class) in ground complete with G.I. fittings including trenching (75 cm deep)and re-filling etc as required				
2.1	50 mm	5.00	Mtr.		
3	Fixing of telephone DP upto 600 pairs on wall / floor with required nut bolts/ fixing arrangements as required complete.	1.00	Nos.		
	Total Rs.				


अधिकाणी अणिवला (नि) E.E. (Plect.
संनिदि सारणी सारणी कनिपु
I.W.D., I.I.I., Kaur

