

QUOTATION

Sub:- Providing & making power outlet and internet points in IME-106 & 107, ESB-II-435 & NL-II-307.

S. No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
(In words & Figures)					
1	Rewiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable and 1.5 sq.mm FRLS PVC insulated copper conductor single core cable as earth wire in existing surface/ recessed steel/PVC conduit including dismantling as required.				
1.01	Group C	4.00	Point		
2	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
2.01	3 x 2.5 sq. mm	10.00	Metre		
2.02	3 x 4 sq. mm	110.00	Metre		
3	Supply and fixing of 32 x 20 mm DLP mini- trunking white-system with independent cover etc. as required complete.	50.00	Meter		
4	Supply and fixing of following accessories suitable for 32 mm x 20 mm size plastic trunking white system.				
4.01	End cap	1.00	Nos.		
4.02	internal / external angle	7.00	Nos.		
4.03	changeable flat angle	4.00	Nos.		
4.04	flat junction	1.00	Nos.		

S. No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
				(In words & Figures)	
5	Laying UTP cable enhanced cat 5/cat 6 cable in existing steel conduit pipe/GI pipe/ raceway / RCC pipe as reqd. the cost shall also include numbering of networking wire from room to rack as reqd. (wire will be supplied by dept)	100.00	Meter		
6	Fixing of RJ-45 modular box with cover plate or I/o box for internet on surface/ recessed cutting the wall making good the same as required. (box and cover plate will be supplied by dept.)	3.00	Nos.		
7	Supply and fixing of following LED light fixture with efficiency >100 lumen/ watt, P.F. >0.95, THD<10%, Electronic driver, LED lamp, reflector, diffuser, MS body/housing holder etc. complete with all fixing accessories and lamp as required complete.				
7.01	36 watt surface mounting LED light fixture 300 x 1200 mm	2.00	Nos.		
8	Supplying, installation of Clip-on frame with finishing plate for 85mm cover for DLP plastic trunking 105mm x 50mm etc. as reqd.				
8.01	3 module	5.00	Nos.		
9	Supplying and fixing following modular switch/ socket on the existing clip-on frame fixed on 85mm cover of 105 x 50 mm DLP plastic trunking including connections etc. as required complete.				
9.01	20 A switch	5.00	No.		
9.02	6/16 A 3 pin socket outlet	5.00	No.		
10.00	Supplying and fixing following size/ modules, plastic box for modular switches in recess etc as required.				
10.01	6 Module	6.00	Nos.		

S. No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
				(In words & Figures)	
11	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
11.01	5/6 A switch	8.00	No.		
11.02	15/16 A switch	6.00	No.		
11.03	3 pin 5/6 A socket outlet	4.00	No.		
11.04	6 pin 15/16 A socket outlet	6.00	No.		
11.05	Blanking Plate	2.00	No.		
12	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.				
12.01	6 Module	6.00	No.		
13	Supply and installation of 400mm sweep AC 230/250 volts, 50 Hz wall mounting revolving fan with brackets etc complete.	2.00	Nos.		
	Total Rs.				_____



6
 अधीक्षक अभियन्ता/S.E.
 संचालक (I.W.D.)
 भाग्योदय संस्थान, कानपुर
 I.I.T., Kanpur
