

INDIAN INSTITUTE OF TECHNOLOGY, KANPUR
INSTITUTE WORKS DEPARTMENT
DIVISION-I

Sl.	Description of items	Unit	Quantity	Rate	Amount
	Minor civil maintenance work				
1.	Providing & fixing in position cladding over lift entrance wall with aluminium composite sheet approved colour and shade made out of 3 mm thick aluminium composite panel material consisting of mineral core sandwich between two aluminium sheets (each 0.5 mm thick) using stainless steel screws nuts, bolts, washers cleats weather silicon sealant etc. The ACP sheet fix over lift cladding wall, fastening with brackets of aluminium tube of required size with necessary fasteners & screw etc complete all as per drawing & direction of Engineer-in-charge. The item includes all cost of material & labour component etc.	Sqm	43.66		
	GST @ _____				
	Total				

Sharma

Executive Engineer