

QUOTATION

Name of work :- Replacement of damaged service cable of Post office and other associated works..

S.No	Description of Items	Qty	Unit	Rate (In words & Figures)	Amount
1	Supplying and making indoor end termination with brass compression gland, aluminum lugs for following size of PVC insulated & PVC sheathed/XLPE aluminum cable of 1.1kV grade as reqd.				
a	3½x25 sq.mm.	2.00	Nos.		
2	Providing and fixing following sizes of PVC casing and capping on surface as reqd.				
a	20 x 12 mm	30.00	Mtr.		
3	Dismantling damaged DB/TPN Switches/ loose wire boxes along with all accessories and depositing the same in the store as reqd.	3.00	Nos.		
4	Supplying and fixing 40 amp to 63 amp rating 240 volts 'C' curve 10 kA MCB of following pole in the existing MCB DB complete with connection, testing & commissioning etc as reqd.				
a	Four Pole	1.00	Nos.		
5	Supplying & Laying of one no. XLPE sheathed aluminum conductor steel armoured power cable of size 3½x25 sq.mm. 1.1kV grade in following manners.				
a	direct in ground I/c excavation, sand cushioning, protective covering and refilling the trench etc. as reqd.	25.00	Mtr.		
b	In pipe	2.00	Mtr.		
c	In open duct	2.00	Mtr.		

9

S.No	Description of Items	Qty	Unit	Rate	Amount
				(In words & Figures)	

d	On surface with MS clamp	10.00	Mtr.		
---	--------------------------	-------	------	--	--

6	Suppling & Fixing, connecting and commissioning of change over switch 100A, 415V TPN 4 pole with side handle switch fuse unit :rewirable in steel sheet enclosure etc as reqd. complete.	1.00	Nos		
---	--	------	-----	--	--

Total Rs

अधीक्ष- अभियन्ता / S.E.
स०नि०वि० (I.W.D.)
भा०प्रौ० सस्थान, कानपुर
I.I.T., Kanpur

(2)

[Handwritten signature]